

ATLAS MOBILE CONCRETE BATCHING PLANTS WITH REVERSIBLE DRUM MIXER

Model	AMCB 10	AMCB 15	AMCB 20	AMCB 25
Output	8-10 m ³ /hr.	12-15 m ³ /hr.	15-20 m ³ /hr.	20-25 m ³ /hr.
Type of mixer	Reversible drum	Reversible drum	Reversible drum	Reversible drum
Unmixed capacity	500 liters	800 liters	1000 liters	1400 liters
Mixed capacity	400 liters	600 liters	800 liters	1000 liters
Rotary speed of mixing drum	20 RPM	20 RPM	17 RPM	17 RPM
Frame and chassis	All structural steel	All rigid steel tube	All rigid steel tube	All rigid steel tube
Weighing conveyor	To feed aggregate from storage bins to mixer	To feed aggregate from storage bins to mixer	To feed aggregate from storage bins to mixer	To feed aggregate from storage bins to mixer
Weighing system	Digital load cell based weighing system	Digital load cell based weighing system	Digital load cell based weighing system	Digital load cell based weighing system
Aggregate storage bin and capacity	4 x 2.5 m ³ each	4 x 3.5 m ³ each	4 x 4.5 m ³ each	4 x 4.5 m ³ each
Water dozing system	Automized	Automized	Automized	Automized
Drum guide roller	3 nos.	5 nos.	6 nos.	6 nos.
Admixer dozing system	Automized	Automized	Automized	Automized
Cement feeding system	Screw conveyor feeding & auto controlled load cell based digital weighing	Screw conveyor feeding & auto controlled load cell based digital weighing	Screw conveyor feeding & auto controlled load cell based digital weighing	Screw conveyor feeding & auto controlled load cell based digital weighing
Power required	35 HP	40 HP	45 HP	55 HP

With Atlas's policy of constant upgradation of products, specifications are subject to change without prior notice.

Accessories shown are optional and not a part of standard supply.